



# Cement Mill Test Report

Date of Issue: November 10, 2023

Plant: Exshaw AB  
 Product: Portland Cement Type I/II/V  
 Mill Test Report Number: MTR-I/II/V-2023-09  
 Manufactured during the month of: October 2023

## ASTM C 150-22 and AASHTO M 85-22 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Rapid Method, X-Ray (C114)			Air content of mortar (%) (C185)		
SiO <sub>2</sub> (%)	---	19.2		12 max	6
Al <sub>2</sub> O <sub>3</sub> (%)	6.0 max	4.0	Blaine Fineness (m <sup>2</sup> /kg) (C204)		
Fe <sub>2</sub> O <sub>3</sub> (%)	6.0 max	3.6		260 min	409
CaO (%)	---	62.0	Passing 45 μm (%) (C430)		
MgO (%)	6.0 max	4.7		---	97.2
SO <sub>3</sub> (%)	2.3 max *	3.0	Autoclave Expansion (%) (C151)**		
Loss on Ignition (%)	3.5 max	2.6		0.80 max	0.19
Insoluble Residue (%)*	1.5 max	0.2	Compressive strength (MPa, [psi]) (C 109)		
CO <sub>2</sub> (%)	---	1.9			
Limestone (%)	5.0 max	4.4	3 days		
CaCO <sub>3</sub> in Limestone (%)	70 min	96.0		12.0 [1740] min	28.2 [4090]
Inorganic Process Addition (Lafarge Cement Kiln Dust)	5.0 max		7 days		
				19.0 [2760] min	34.3 [4980]
			28 days (Reflects previous month's data)		
					44.1 [6392]
Adjusted Potential Phase Composition (C 50)			Time of setting (minutes)		
C <sub>3</sub> S (%)	---	58	Vicat Initial (C191)		
C <sub>2</sub> S (%)	---	11		45 - 375	89
C <sub>3</sub> A (%)	5 max	4	Sulfate Resistance (%) (C452)**		
C <sub>4</sub> AF (%)	---	11		0.040 max	0.028
C <sub>4</sub> AF + 2(C <sub>3</sub> A)	25 max	20	Mortar Bar Expansion (%) (C1038)**		
C <sub>3</sub> S+4.75*C <sub>3</sub> A (%)	100 max	78		0.020 max	0.010
ASTM C 150-17 and AASHTO M 85-17 Optional Requirements:					
NaEq (%)	0.60 max	0.56	False set (%) (C451)		
				50 min	90

\* May exceed the SO<sub>3</sub> maximum based on C 1038 results of <0.020% expansion at 14 days.

\*\* Current Production run not available - most recent provided



Certified to  
NSF/ANSI/CAN 61

AASHTO  
ACCREDITED

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of:

ASTM C 150-22 & AASHTO M 85-22 STANDARD SPECIFICATIONS FOR TYPES I, II & V CEMENTS; and  
 ASTM C 150-22 & AASHTO M 85-22 OPTIONAL CHEMICAL REQUIREMENTS FOR TYPES I, II & V LOW ALKALI CEMENT.

Western Canada BU - Exshaw Plant  
 P.O. Box 160, Highway 1A, Exshaw AB, T0L 2C0  
 Phone: 403-673-3815

Certified By:

John W Blair  
 Quality Manager



# Cement Mill Test Report

Date of Issue: November 10, 2023

**Plant:** Exshaw AB  
**Product:** Portland Cement Type I/II/V  
**Mill Test Report Number:** MTR-I/II/V-2023-09  
**Manufactured:** October 2023

## ASTM C 150-22 and AASHTO M 85-22 Standard Requirements

### Additional Data

Item	Test Result	
	Limestone	Inorganic Process Addition Lafarge Cement Kiln Dust
Amount (%)	4.4	-
SiO <sub>2</sub> (%)	2.2	n/a
Al <sub>2</sub> O <sub>3</sub> (%)	0.6	n/a
Fe <sub>2</sub> O <sub>3</sub> (%)	0.2	n/a
CaO (%)	49.5	n/a
SO <sub>3</sub> (%)	0.1	n/a
CO <sub>2</sub> (%)	42.3	n/a

### Base Cement Phase Composition

Item	Test Result
C <sub>3</sub> S (%)	61
C <sub>2</sub> S (%)	12
C <sub>3</sub> A (%)	5
C <sub>4</sub> AF (%)	11

We certify that the data above reflects the materials used in cement manufacture during the production period indicated.

Note: Specific Gravity for Portland Cements is 3.14

Western Canada BU - Exshaw Plant  
P.O. Box 160, Highway 1A, Exshaw AB, T0L 2C0  
Phone: 403-673-3815

Certified By:

  
John W Blair  
Quality Manager